

M/s Diamond Cements (Prop. HeidelbergCement India Limited)

Clinkerisation Unit, Narsingarh

Month: June 18

TEST REPORT OF STACK MONITORING

Location	S-1	S-2	S-3
Date of Monitoring	09.06.2018	07.06.2018	16.06.2018
Stack Attached to	Bag House of Coal Mill No.-1	Bag House of Coal Mill No.-2	Bag House of Coal Mill No.-3
Particulate Matter (mg/Nm³) Isokinetic Samples	12.0	22.7	21.2

Location	S-4	S-5	S-6
Date of Monitoring	12.06.2018	08.06.2018	20.06.2018
Stack Attached to	Hybrid Filter of Kiln/Raw Mill No. -1	Hybrid Filter of Kiln/Raw Mill No. -2	Reverse Air Bag House (RABH) of Kiln/Raw Mill No. -3
Particulate Matter (mg/Nm³) Isokinetic Samples	24.0	28.0	18.7

Location	S-7	S-8	S-9	S-10
Date of Monitoring	12.06.2018	08.06.2018	16.06.2018	19.06.2018
Stack Attached to	ESP of Clinker Cooler No.-1	ESP of Clinker Cooler No.-2	ESP of Clinker Cooler No.-3	Bag House of Crusher
Particulate Matter (mg/Nm³) Isokinetic Samples	27.5	20.8	26.1	17.2

** Plant was under planned shutdown, Hence Stack Monitoring could not be conducted.

M/s Diamond Cements (Prop. HeidelbergCement India Limited)

Grinding Unit, Imlai

Month: June 18

TEST REPORT OF STACK MONITORING

Location	S-1	S-2	S-3
Date of Monitoring	09.06.2018	09.06.2018	22.06.2018
Stack Attached to	Bag House of Cement Mill No.-1	Bag House of Cement Mill No.-2	Bag House of Cement Mill No.-3
Particulate Matter (mg/Nm³) Isokinetic Samples	11.2	13.8	17.2

Location	S-4
Date of Monitoring	13.06.2018
Stack Attached to	Bag House of Packing Plant No.- 3
Particulate Matter (mg/Nm³) Isokinetic Samples	22.1

M/s Diamond Cements (Prop. HeidelbergCement India Limited)

Lime Stone Mines, Patharia

TEST REPORT OF STACK MONITORING

Month: June 18

Location	S-1
Date of Monitoring	22.06.2018
Stack Attached to	Bag House of Crusher
Particulate Matter (mg/Nm³) Isokinetic samples	25.6