

for better building

HCIL(NGH)-QCD-F026

**DIAMOND CEMENTS (Prop. HEIDELBERGCEMENT INDIA LTD)  
DAMOH UNIT**

**TEST REPORT FOR MYCEM**

Portland Pozzolana Cement as per IS1489 (Part I):2015

REF.: DC/DMH/QA/2021/25

DATE : 31.07.2021


WEEK NO. : 25

(18.06.21-24.06.21)

| CHARACTERISTIC   | RESULTS OBTAINED | REQUIREMENT OF IS1489 (Part 1):2015   |
|--|------------------|---|
| <b>(A) CHEMICAL COMPOSITION</b>                        |                  |   |
| (i) Loss on Ignition % by mass                         | 2.48             | 5.0, Max.   |
| (ii) Magnesia (MgO), % by mass                         | 2.91             | 6.0, Max.   |
| (iii) Sulphuric Anhydride (SO <sub>3</sub> ) % by mass | 2.36             | 3.5, Max.   |
| (iv) Total Chloride (Cl), % by mass                    | 0.016            | 0.1, Max.   |
| (v) Insoluble Material, % by mass                      | 33.52            | $\bar{X} + 4.0 \times (100 - \bar{X}) / 100$ Max<br><br>0.6 X Min<br>Where $\bar{X}$ is the declared % of Fly Ash in the PPC sample |
| <b>(B) PHYSICAL TESTING</b>                            |                  |   |
| <b>1. Fineness of Cement</b>                           |                  |   |
| Sp. Surface blaine (m <sup>2</sup> /kg)                | 330              | 300 m <sup>2</sup> /kg minimum  |
| <b>2. Soundness</b>                                    |                  |   |
| Le-Chatelier Expansion (mm)                            | 0.50             | 10 mm, Max.   |
| Autoclave Expansion (%)                                | 0.046            | 0.8 %, Max.   |
| <b>3. Setting Time</b>                                 |                  |   |
| Initial (in Minutes)                                   | 185              | 30 minutes, Min.  |
| Final (in Minutes)                                     | 235              | 600 minutes, Max.   |
| <b>4. Compressive Strength (MPa)</b>                   |                  |   |
| (a) At 72 ± 1 Hrs.                                     | 28               | 16 MPa, Min.  |
| (b) At 168 ± 2 Hrs.                                    | 37               | 22 MPa, Min.  |
| (c) At 672 ± 4 Hrs.                                    | 48               | 33 MPa, Min.  |
| <b>5. Drying Shrinkage (%)</b>                         | 0.042            | 0.15 %, Max.  |
| <b>6. Declared % of Fly Ash in PPC</b>                 | 34.95            | 15 - 35 %   |

**Remarks :**

- Temperature during testing - 27 ± 2° c.
- The amount of Fly Ash in the finished cement is not varying more than ± 3% from the declared value.
- Portland Pozzolana Cement conforms to the requirement of IS 1489 (Part 1):2015 in all respects.



Head of Quality Control - Damoh